

SCHEDULE OF EVENTS


Building your project within 8 - 12 weeks is our goal. The following are approximate time frames.

- 1 Engineering, surveys, permits and approval process (approx. 4 6 weeks)
- 2 Dig retaining wall footer and get inspection (approx. 2 3 days, if applicable)
- 3 Pour concrete footer (approx. 1 day, if applicable)
- 4 Install retaining wall block and inspection (approx. 1 day, if applicable)
- 5 Fill concrete into block wall cells (approx. 1 day, if applicable)
- 6 Layout / Dig (**PAYMENT DUE**) (Time frame starts now) / Steel (approx. 1 2 weeks)
- 7 Steel, ground and pressure test inspection (approx 1 day)
- 8 Shoot Gunite or Shotcrete Shell (**PAYMENT DUE**) (approx. 1 day)
- 9 Deck grade (Strip & remove wood around shell / backfill dirt) (approx. 3 days)
- 10 Install plumbing (approx. 1 week)
- 11 Install tile (approx. 1 week)
- 12 Form a footer for screen (if applicable) and bond pool & decking (approx. 4 days)
- 13 Footer and deck inspection (approx. 1 day)
- 14 Pour footer, decking (if concrete deck) and equipment slab (approx. 1 day)
- 15 Install coping and paver deck (if applicable) (approx. 1 week) (**PAYMENT DUE**)











SCHEDULE OF EVENTS (cont.)

- 16 Install fence or screen (approx. 1 week, if applicable)
- 17 Install and plumb-in pump equipment (approx. 1 - 2 days)
- Electrical hook-up of all equipment (approx. 1 2 days) 18
- 19 Install baby fence or alarms by code (approx. 1 day)
- 20 **Electrical and safety barrier inspection** (Baby fence or alarms) (approx. 1 day) Note: Homeowner must be home for Hook-up and Inspection
- 21 Pool cleaned out, scraped, sealed and prepped (approx. 1 - 2 days)
- 22 Install pool interior surface (approx. 1 day)
- 23 **Start filling pool** (Takes approx. 24 hours to fill) (**FINAL PAYMENT DUE**)
- 24 Start up, apply first dose of chemicals, adjust all valves for proper operation, program system and fine tune (approx. 1 week process)

Note: Start-up date is when all warranties are activated.

- 25 Final grading, clean up and have dumpster removed (approx. 2 days)
- 26 Sprinklers, sod, landscape and/or hay & seed property (By others)
- 27 Get final surveys and survey approval by building department (approx. 2 weeks)
- 28 Pool school (Set appointment for approx. 1 month after start-up date)
- 29 Walk through with homeowner at residence (Set appointment with supervisor)
- 30 Call for final inspection (within approx. 30 days)

Since 2006, NO pools have gone over a 12 week construction time frame.